GOVERNMENT OF ANDHRA PRADESH
ABSTRACT

Water Resources Department – SRBC – Construction of Sri Narasimharaya Sagar (GBR) Project – Formation of Loading berm along the d/s of dam from Ch 2450 m to Ch 2950 m – Administrative Approval – Accorded – Orders – Issued.

WATER RESOURCES (PROJECTS.III) DEPARTMENT

G.O.RT.No. 200 Dated: 20-03-2018

Read the following:-

1) GO Rt No.771, WR (Proj.III) Dept., dt:20.12.2016.
2) From the Chief Engineer (P), Kurnool Lr.No. WRD-TW0GBR(MIS)/27/2017-DEE3-AEE7, dt:25/11/2017.

&&&&

In the GO 1st read above, the Government have accorded administrative approval for the work of "SRBC – Construction of Sri Narasimharaya Sagar (GBR) Project – Formation of Loading berm along the d/s of dam from Ch 2450 m to Ch 2950 m" for an amount of Rs.45,90,00,000/- subject to condition that the Chief Engineer (P), Kurnool shall accord Technical sanction based on the working drawings of the CE/CDO.

2. In the reference 2nd read above, the Chief Engineer (P), Kurnool has requested the Government to accord administrative approval for the work "Investigation, Designing & Construction of Sri Narasimharaya Sagar (GBR) Project- Formation of loading berm along with d/s of dam from Ch 2950 m to Ch 2965 m (15m)" for an amount of Rs.1,32,03,261/-.

3. The Government after careful examination of the proposal of Chief Engineer (Projects), Kurnool, hereby accord administrative approval for the work "Investigation, Designing & Construction of Sri Narasimharaya Sagar (GBR) Project- Formation of loading berm along with d/s of dam from Ch 2950 m to Ch 2965 m (15m)" for an amount of **Rs.1,40,30,609/- (Rupees One Crore Forty Lakhs Thirty Thousand Six hundred and Nine only)** *as per the details mentioned in Annexure* **subject to the following conditions:**

i) The Chief Engineer (P), Kurnool shall ensure the correctness of provisions, quantities and Rates, Labour Cess reimbursement shall be as per the decision taken during the Secretaries' meeting held on 27-8-2011.

ii) The Chief Engineer (P), Kurnool shall entrust the subject work duly following the transparent tender process.

4. The above expenditure is debitable to the head of account "MH 4700 Capital Outlay on Major Irrigation – (01) Major Irrigation – Commercial – M.H.121 Srisailam Right Branch Canal (Neelam Sanjeeva Reddy Sagar) – G.H.11 State Development Schemes – S.H. (26) Dam and Appurtenant Works – 530 Major Works – 531 Other Expenditure".

5. The Chief Engineer (Projects), Kurnool shall take further action accordingly.

6. This order issues with the concurrence of Finance (FMU.WR.II) Department vide their UO No. 48022/439/FMU.WR.II/2016, dt:18.03.2018.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

SHASHI BHUSHAN KUMAR
SECRETARY TO GOVERNMENT

To
The Chief Engineer (Projects), Kurnool
Copy to:
The Director of Works & Accounts, Vijayawada
The Finance (FMU.WR.II) Department
The Accountant General, AP, Hyderabad
The PS to Hon'ble Minister (WRD)
The PS to Secy (WRD)
File No.12525/Proj.III/Narasimharayasagar/2016
SF/SC

//FORWARDED :: BY ORDER//

SECTION OFFICER

ANNEXURE TO GO RT NO.200, WATER RESOURCES (PROJ.III) DEPT., DATED:20.03.2018 REGARDING ADMINISTRATIVE APPROVAL FOR THE WORK "CONSTRUCTION OF SRI NARASIMHARAYA SAGAR (GBR) PROJECT – FORMATION OF LOADING BERM ALONG THE D/S OF DAM FROM CH 2450 M TO CH 2950 M"

S No.	Item description	Rate/Unit	Amount in Rs.
(A)			
1)	Excavation and removal of silt or silt mixed with sand in slussy condition from canal bed including disposing off the same in spoil bank or on the canal embankment in layers as directed etc., complete with initial lead upto 50m and all lifts.	237.62	1,76,742
2)	Providing and constructing 2m thick chimney and filters using clean approved sand satisfying filter criteria including cost of all materials, machinery, labour compacting etc., complete with initial lead upto 50m and all lifts.	1924.60	73,01,211
3)	Providing and constructing graded filter media below and behind rock toe consisting of 30 cm thick 80-20 mm size graded coarse aggregates satisfying filter criteria as per specifications including cost of all materials, labour, machinery, laying to required slope, compaction etc., complete with initial lead upto 50m and all lifts.	1165.50	-29,627
4)	Providing and constructing graded filter media below Sand blankets consisting of 250mm thick of two layers 80-10 mm size graded coarse aggregates satisfying filter criteria as per specifications including cost of all materials, labour, machinery, laying to required slope, compaction etc., complete with initial lead upto 50m and all lifts.	1165.50	7,14,816
5)	Providing and constructing dry rock pitching using un-coursed rubble stone of size 300mm thick and uncoursed rubble stone chips from dump to site of work & rolling including cost of all materials, machinery, labour, hand packing rubble and stone & chips, to the designed profile with all leads and lifts etc.,	600.40	-78,166
6)	Providing and constructing dry rock pitching using Un-coursed rubble stone of size 25 to 900 mm thick and uncoursed rubble stone chips from dump to site of work & rolling including cost of all materials, machinery, labour, hand packing rubble and stone & chips to the designed profile with all leads and lifts etc.,	579.71	33,93,374
		Total:	1,14,78,350
		Add Tender Excess at 2.97%	3,40,907
	Total (A)		**1,18,19,257**
(B)			
1)	Provision for GST 12%		14,18,311
2)	Provision for Labour Cess @1%		1,18,193
3)	Provision for NAC @ 0.1%		11,819
4)	Provision for Seigniorage charges		6,63,029
	Total (B)		**22,11,352**
	GRAND TOTAL (A+B)		**1,40,30,609**

(Rupees One Crore Forty Lakhs Thirty Thousand Six hundred and Nine only)

SHASHI BHUSHAN KUMAR
SECRETARY TO GOVERNMENT